

New Industrial Units, Bristol



Project Details

Material Specification

8,650t of SHW Clause 803 Type 1 Subbase Limestone Blend.

Overview

Construction of two new industrial units with access roads, parking and pathways.

Delivery Partner Drumlisch Limited.

Supply Period May 2022.

Construction

Incinerator Bottom Ash Aggregate (IBAA) was supplied from our Blue Phoenix Severnside plant in Bristol. IBAA/LB Type 1 Subbase was supplied across the site at an average depth of 150mm to 200mm, which was overlayed by 200mm asphalt on the roads, 100mm on the pathways and 225mm of concrete on the structural platform.

